

Quote Request

Installation of Roll In Shower at 1314 Westfield

Quotes due January 21, 2014 @ 2:00 p.m.

Fax to Corinne Lisefski at (412) 456-5007

Scope of Work

Location: 1314 Westfield Pittsburgh PA 15216

Work:

- Tear out existing floor covering and shower unit and thoroughly clean and prepare floor and area where shower will be installed.
- Furnish and install new Schluter waterproofing system in the shower area and bathroom floor,
- Furnish and install a new 12x12 ceramic tile floor in the bathroom,
- Furnish and install a new mosaic tile 2x2 in the shower floor, shower to be 30 X 60”.
- Furnish and install new smooth white acrylic shower walls from floor to ceiling.
- Furnish and install new high quality collapsible continuous foam water dam at the outside edge of the shower, professionally cut at the edges, and sealed with white beaded silicon grade caulking.
- Replace existing shower valve with a chrome finish Delta Lahara Fixture Kit (or approved equal).
- Furnish and install new shower valve with handheld showerhead, length to reach all areas (minimum 60 inches), with pause or shut off at the hand held showerhead.
- Provide and install blocking for grab bars and three grab bars 12", 12", and 24" (24" is optional). Location will be determined during installation. Provide and install a continuous U shaped grab bar, 1 1/2 "dia. X 10' for the 3 sides of the shower.
- Furnish and install a new permanently mounted AKW Wide Padded Fold Up Shower Seat with Back and Arms, Blue (http://www.amazon.com/gp/offer-listing/B001AJ9IH6/ref=dp_olp_new?ie=UTF8&condition=new) (or approved equal) located on the back of the shower close to where the shower meets the bathroom wall for easy transfer from a wheelchair.
- Reinstall shower curtain rod or install a new one if needed
- Apply sealant as needed.
- All plumbing is to be reconnected to present service.
- Keep existing toilet, pedestal sink, mirror, and lights. There is to be no wall work or wall covering to be done on this project.
- Contactor will be provided assess and work with Site Management as restoration is being performed.
- All work to be coordinated through site manager
- Work to be completed within 5 working days
- Vendor is responsible for cleanup and hauling away of debris

Installation of Roll In Shower at 1314 Westfield

Due: 1/21/14 @ 2 pm

Work: (Continued)

- No debris to be placed in HACCP trash receptacles.
- All work to be done in accordance with Manufacturer’s specifications and to meet local building codes
- All work to be in compliance with UFAS specifications
- Vendor is responsible for obtaining all required permits

Site Visit: Jan. 15, 2014 at 2 pm at Location

Total Bid amount for all work: \$ _____

Total Bid amount _____ **dollars**
In words

Contract award will be based on total bid amount

(Please print clearly)

Company Name: _____

Signature: _____

Print Name: _____
(of person signing)

Address: _____
(of company)

Phone Number: _____ Fax: _____

Email: _____

Please contact Corinne Lisefski at 412.456.5000 ext 8546 with any questions about the above scope.