

Quote Request

Removal and Construction of deck at Fairview St.

Quotes due July 3, 2013 @ 2:00 p.m.

Fax to Corinne Lisefski at (412) 456-5007

Scope of Work

Location: 208-214 Fairview St. Pittsburgh, PA 15220

Work

- Demolition of existing deck and stairs attached to property(houses, 208, 210, 212, and 214). Measuring approximately 12' x 4' w/2-1/2' x 4' bump out at top of steps and existing three steps to driveway located in the rear of each unit.
- Constructed new deck using all treated lumber measuring approx. 12' x 4' with 2-1/2' x 4' bum out at top of stairs. With set of stairs to driveway three (3) treads with risers and railing on one side and railing on balance of deck approx. 22' of railing. Deck to be supported using 6" x6" posts hat with 2" x 10" beam and deck double 2" x 10" beam.
- Deck to be lag bolted into existing structure of unit. New deck to be pressure washed and clear sealant to be applied immediately following construction
- See attached drawing

- All work to be done professionally
- No debris to be placed in HACP trash receptacles
- All work to be done in accordance with the HACP specifications
- Contractor is responsible for clean-up to work site and damages to yard and lawn as a result of construction
- Vendor is responsible for obtaining all required permits

Site Visit: Mon, July 1, 2013 at 2 pm.at location

Please contact Corinne Lisefski at 412.456.5000 ext 8546 with any questions about the above scope.

Quote Request

Removal and Construction of deck at Fairview St.

Due: 7/3/13 at 2 pm

Total Bid amount for all work: \$ _____

Total Bid amount _____ dollars
In words

Contract award will be based on total bid amount

(Please print clearly)

Company Name: _____

Signature: _____

Print Name: _____
(of person signing)

Address: _____
(of company)

Phone Number: _____ Fax: _____

Email: _____