

Quote Request

Concrete Step Replacement at 315 Rochele Str

Quotes due September 27, 2017 @ 10:00AM



Fax to Debbie Norkevicius at (412) 456-5007

Scope of Work

Removal and installation of 15 steps 48" x 11" tread x 7 3/4" to front entrance of unit located at 315 Rochele Street, Pittsburgh, PA 15210. The steps to be replaced are divided into two (2) sections with 11 (eleven) steps 48 1/2" wide X 11" tread and 7 3/4" riser. This section has cheek walls on each side and should be left intact. The remaining four (4) steps lead to front porch. Contractor is responsible for removal of all debris and to include sealing new aggregate.

Task List:

Each task has been assigned a number for reference throughout the rest of this document and during the commission of the project

1. Preparation of site for demolition and resident access.
2. Concrete steps to be formed at 48" wide x 7-3-3/4" riser with 11" tread to have broom or other non-skid finish. Contractor is responsible to protect finish until concrete has dried.

Remove existing concrete steps total of 48" x 11" tread x 7 3/4" tall.

Contractor should take precautions as to not disturb cheek walls on each side of steps. Contractor should be aware that unit is occupied and make preparations to give occupant access to unit.

**Site Visit: September 18, 2017 @ 11:00 AM – 315 Rochele Street,
Pittsburgh, PA 15219**

****Please have photo identification available upon request.**

For more information or questions, please contact Debbie Norkevicius @
412-456-5000 X 8505 or Debbie.Norkevicius@HACP.org

Quote Request

Concrete Step Replacement at 315 Rochele Str

Quotes due 9/27/2017 @ 10:00AM

Total Cost: \$ _____

Total Cost: \$ _____
(in words)

Contract award will be based on lowest average bid amount

(Please print clearly)

Company Name: _____

Address: _____
(of company)

Signature: _____

Print Name: _____
(of person signing)

Phone Number: _____ Fax: _____

Email: _____