

Quote Request

Concrete Work and Leveling at Various Scatter Sites REBID

Quotes due November 3, 2015 @ 2:00 p.m.

Fax to Debbie Norkevicius at (412) 456-5007

Scope of Services

Please provide the following services:

218 Clover Street - Pittsburgh, PA 15210

- **Concrete Description**

- There are 2 expansion joints in middle of front walk that need ground out/cleaned out and caulked to keep water from running beneath and disturbing the foundation and sub-base.

216 Clover Street - Pittsburgh, PA 15210

- **Concrete Description**

- The front stoop slab has a void under it. This is due to settlement and compaction of the sub base beneath the concrete, which has led to the existence of voids. There is a separation between stoop and house that needs ground out/cleaned out and caulked to keep water from running beneath the slabs and continuing to deteriorate the sub base.

2700-2702 Sacramento Dr. - Pittsburgh, PA 15204

- **Concrete Description**

- Front stoop and approx. 6 walkway slabs have sunken and created trip hazards. This is due to settlement and compaction of the sub base beneath the concrete, which has led to the existence of voids. There are 2 joints in walkway that need ground out/cleaned out and caulked to keep water from running beneath the slabs and continuing to deteriorate the sub base.

208-210 Fairview Dr. - Pittsburgh, PA 15204

- **Concrete Description**

- Approximately 1 driveway slab, 2 walkway at driveway/road, and 2 small slabs between the driveway and stoop, and the sidewalk along the road between 212 and 214 have sunken, shifted and created uneven transitions between the slabs. This is due to settlement and compaction of the sub base, which has led to the existence of voids beneath concrete.

746 Litchfield St. - Pittsburgh, Pa. 15204

- **Concrete Description**

- Leveling of Approximately 3 slabs of front walway and set of 9 steps

714-716 Valonia Street Pittsburgh, PA 15205

- **Concrete Description**

- Front Steps on both units have sunken due to settlement and compaction of the sub base beneath the concrete, which has led to the existence of voids.

Quote Request

Concrete Work and Leveling at Various Scatter Sites REBID

(Quotes Due 11/03/15/ @ 2PM)

- Haul away debris (Debris is not to be placed in HACP trash receptacles) for all sites
- All work is to be professionally done
- All work is to be coordinated with the Site Manager
- Vendor is responsible for obtaining all required permits

SITE VISIT ON October 29, 2015 @ 10:00AM (Please meet at 216 Clover Street, Pittsburgh, PA 15210)

COST OF PREPARATION OF QUOTE: All costs incurred, directly or indirectly, by the bidder in responding to or inquiring about this quote, including, travel, preparation, communication, consultation, design, submission, and miscellaneous expenses, shall be the sole responsibility of the bidder and shall be borne by the bidder. HACP will not reimburse the bidder for said cost.

Please contact Debbie Norkevicius at 412-456-5000 Ext. 8505 or Debbie.Norkevicius@HACP.org with any questions about the above scope.

Total for All Work: \$ _____

Total for All Work: _____
(in words)

Contract award will be based on lowest total bid amount

(Please print clearly)

Company Name: _____

Address: _____
(of company)

Signature: _____

Print Name: _____
(of person signing)

Phone Number: _____ Fax: _____

Email: _____