

Quote Request

Police Sub Station – Masonry Work

Quotes due May 9, 2018 @ 10:00am



Fax to Brandon Havranek at (412) 456-5007

Scope of Work

441 Mt. Pleasant Rd. Police Station

Scope of work to be performed: build scaffolding inside as needed, stock block as needed inside station, lay 8" & 6" block per plans for new block walls, install joint reinforcing per plans, wall is approximately 22' long and 8' high, lay concrete lintels above door and windows at specified height, cut out existing concrete in basement in 8 areas, approximate cutout to be 2.5' square and to a depth of 16", install 10 mil plastic and overlap existing, install rebar to tie-in with existing floor, install rebar into footer per plans, pour new 4000psi concrete footer for post, and grout in cells of new block wall, embed new anchor bolts, place non shrink grout as needed, set (7) new 8' high post jacks and plumb/ level. Clean up jobsite and remove any job related materials.

Drawing M-102 Second Floor Plan

Cut 44" x 32" opening for outdoor air intake and discharge louver on second floor furnace.

A site visit will be on **May 4, 2018 at 10:00AM** at Northview Heights, 441 Mt. Pleasant Rd, Pittsburgh, PA 15214.

**Please have photo identification available

Plans will be available on site

Project must be completed by May 20, 2018

For more information or questions, please contact Brandon Havranek @ 412-456-5000 x8546 or Brandon.Havranek@HACP.org

Quote Request

Police Sub Station – Masonry Work

Quotes due May 9, 2018 @ 10:00am

Total Cost: \$ _____

Total Cost: \$ _____
(in words)

Contract award will be based on lowest responsive and responsible bid amount

(Please print clearly)

Company Name: _____

Address: _____
(of company)

Signature: _____

Print Name: _____
(of person signing)

Phone Number: _____ Fax: _____

Email: _____