#### H.A.C.P.

# Emergency Support, Snow Removal/Salting Services

## Scope of Work

#### Locations

Contractor shall be responsible for performing the following activities at the listed sites as individually requested:

#### Driveways, parking lot areas, steps and sidewalks.

- 1. Bedford Hope Center, 2305 Bedford Avenue, Pittsburgh PA 15219
- 2. Facility Services Building, 201 Kirkpatrick St, Pittsburgh PA 15219
- 3. DOC Center, 1205 Liverpool St, Pittsburgh PA 15233
- 4. Gualtieri Manor, 2125 Los Angeles Ave, Pittsburgh PA 15216
- 5. Murray Towers, 2825 Murray Ave, Pittsburgh PA 15217
- 6. Glen Hazel High Rise, 945 Roselle Ct, Pittsburgh PA 15207
- 7. Carrick Regency, 2129 Brownsville Rd, Pittsburgh PA 15210
- 8. Caliguiri Plaza, 801 E Warrington Ave, Pittsburgh PA 15210
- 9. Northview High Rise, 533 Mt Pleasant Rd, Pittsburgh PA 15214
- 10. Allegheny House, 1305 Allegheny Ave, Pittsburgh PA 15233
- 11. Mazza Pavilion, 920 Brookline Blvd, Pittsburgh PA 15226

## Streets within the Community, driveways, & parking lot areas only.

- 12. Addison Terrace, Pittsburgh PA 15219 (community)
- 13.Bedford Dwellings, Pittsburgh PA 15219 (community)
- 14. Homewood North, Pittsburgh PA 15208 (community)
- 15. Allegheny Dwellings, Pittsburgh PA 15212 (community)
- 16. Northview Heights Estates, Pittsburgh PA 15214 (community)
- 17. Arlington Heights, Pittsburgh PA 15210 (community)
- 18. Scattered sites, Pittsburgh PA (TBD)

### Scope

As requested, removal of all snow/ice and salting of all driveways, parking lot areas, and where stated, steps and sidewalks.

- Contractor will supply all the necessary materials, labor & equipment required to plow and melt any amount of snow or ice
- Contractor will supply at least 2 (two) telephone numbers where they can be reached in the event of an emergency
- Plow and salt entire site when there is an accumulation of 3 (three) or more inches of snow
- Salt entire site when there is an accumulation of 2 (two) inch or less of snow or when freezing conditions occur
- In the event of overnight precipitation by 11:00pm, all driveways, parking areas, sidewalks and steps are to be cleared by 7AM
- In the event of a snow fall during regular business hours, driving lanes will be plowed & salted as is necessary at regular intervals throughout the day
- During any event, contractor should be aware of the elderly tenants with special needs within HACP high rises who may need to navigate at any time
- All equipment is to be licensed, inspected & insured
- All salt is to be supplied on a bulk basis for plowed areas
- Roads, drives, and lots are to be treated with salt
- Sidewalks are to be treated with calcium
- Contractor(s) will work for HACP to maintain snow removal and salting during the duration of any amount of participation.

# ICE, 2010 cost with additional 5%

Cost per application for plowing and sa	altings 250
Cost per application for salting only\$_	115
Cost per application for calcium (sidew	valk only) \$ 72
Cost per application of plowing \$	145
Cost per application for Sidewalk clear	ring and application of calcium <u>\$ 144</u>
Vendor Name:	
Address:	
Print Name:	
Phone Number:	Fax: