


Quote Request

Removal and Replacement of Concrete Steps and Porch Deck



Quotes due October 20, 2020 @ 10:00 A.M.

Email bids to Brandon.Havranek@HACP.org

Scope of Work

The successful contractor will provide complete removal and replacement of concrete steps and front porch deck at **3331 Middletown Rd. Pittsburgh, PA 15204.**

The Scope of Work (SOW) is governed by the specifications described herein:

1. Removal

Contractor is to remove and dispose of approximately 60 sq.ft of broken concrete consisting of porch deck 5'x6' and two (2) steps ea. 5' ft. long as designated by the HACP project manager.

2. Construction

Contractor shall fabricate and install forms to sufficiently contain poured concrete for Porch Deck slab measuring 5'w.x 6'3"d. x 7.5"thick and one step measuring approximately 5'long x 14" tread x 7-1/2"riser & step 2 measuring 13" tread x 9"riser and 5Ft. long.

Concrete is to be reinforced with ½" rebar and wire mesh.

Contractor is to provide non-slip finish (broom/ float. Contractor will be required to repair any and all damage that is occurred during the demolition and installation phase to the existing landscape.

3. No debris to be place in HACP trash receptacles.

4. Contractor is responsible for obtaining all required permits.

Site visit will be held on **October 13, 2020 @ 10:00AM**, please meet at:
3331 Middletown Rd. Pittsburgh, PA 15204

For more information or questions, please contact Brandon Havranek @
412-456-5000 x8546 or Brandon.Havranek@HACP.org

Quote Request

Removal and Replacement of Concrete Steps and Porch Deck

Quotes due 10/20/2020 @ 10:00 A.M.

Total Cost: \$ _____

Total Cost: \$ _____
(in words)

Contract award will be based on lowest responsive and responsible bid amount

(Please print clearly)

Company Name: _____

Address: _____
(of company)

Signature: _____

Print Name: _____
(of person signing)

Phone Number: _____ Fax: _____

Email: _____